

**PLANT LIST**

KEY	QTY	LATIN NAME	COMMON NAME	SIZE	NOTES
<b>TREES</b>					
AC	1	Amelanchier canadensis x grandiflora	'Autumn Brilliance' Serviceberry	7-8' ht.	
BN	3	Betula nigra 'Heritage'	Heritage River Birch	2.5"-3" cal.	b&b
TO	7	Thuja occidentalis 'Emerald'	Emerald Arborvitae	7-8' ht.	b&b
<b>SHRUBS/VINES</b>					
AZ	6	Azalea x 'Delaware Valley White'	Delaware Valley White Azalea	30" ht.	
CJ	1	Clematis 'Jackmanii'	Jackmanii Clematis	3 gal.	
HA	11	Hydrangea arborescens 'Annabelle'	Annabelle Hydrangea	30" ht.	
IC	7	Ilex crenata 'Hetzii'	Hetzi Holly	30" ht.	
RO	6	Rhododendron 'Janet Blair'	Janet Blair Rhododendron	36" ht.	
SB	5	Spiraea bumalda 'Anthony Waterer'	Anthony Waterer	24" ht.	
SM	3	Syringa patula 'Miss Kim'	Miss Kim Lilac	30" ht.	
<b>PERENNIALS/GRASSES</b>					
DP	6	Dennstaedtia punctilobula	Hay-scented Fern	1 gal	
HF	11	Hosta 'Francee'	Francee Hosta	2 gal	
HH	8	Hemerocallis 'Happy Return'	Happy Return Daylily	2 gal.	
LR	60	Liriope muscari 'Big Blue'	Lily Turf	2 qts.	
VM	28	Vinca minor 'Bowles Variety'	Vinca	2 qts.	

**PLANTING NOTES**

- All plant material shall be approved by the Landscape Architect prior to arrival on the site.
- All plant material shall conform to the guidelines established by "The American Standard for Nursery Stock", published by the American Association of Nurserymen, Inc.
- No substitution of plant species will be allowed without the approval of the Landscape Architect.
- The Contractor shall locate and verify all utility line locations prior to staking and report any conflicts to the Landscape Architect.
- All plants shall be staked out in their approximate location by the Contractor. The Contractor shall adjust the locations of these stakes as required by the Landscape Architect to account for subsurface utilities, other field conditions and to achieve design intent. Final locations must be approved by the Landscape Architect prior to planting.
- No planting shall be installed before acceptance of rough grading of topsoil.
- The rootballs of trees shall be planted 3" above adjacent finished grade. Excavate holes no deeper than the rootball of trees. Holes shall be at least 3' greater in diameter than root ball. Backfill planting hole with 'planting mix'. All plants which settle out of plumb or below finished grade shall be immediately replanted.
- The rootballs of shrubs shall be planted 2" above adjacent finished grade. Excavate holes no deeper than the rootball of shrubs.
- All shrubs, groundcovers and perennials shall be planted in continuous planting beds. All beds shall be excavated 12" and the topsoil and subsoil set aside for reuse. Remove all stone and debris from excavated soil. Backfill beds with 12" of 'planting mix' before planting shrubs, perennials and groundcovers.
- 'Planting Mix' shall consist of 2 parts of topsoil saved from site excavations and 1 part compost. Thoroughly mix to create uniform blended mixture. If insufficient topsoil is available on the site, mix existing soil in a ratio of 1 part soil to 1 part compost. Remove all stones and debris larger than 2" from planting mix.
- All beds as shown on the drawings shall be edged with a 4" trench neatly cut and backfilled with bark mulch. All beds shall be covered with no less than 2" depth settled bark mulch and no greater than 3" depth bark mulch.
- All plants are to be thoroughly watered after installation, at least twice within the first 24 hours.



6' Board Fence at side and rear yard



36" Ht. Picket Fence along front yard

