

Design Consultants, Inc.

120 Middlesex Avenue
Somerville, MA 02145
(617) 776-3350

MEMORANDUM

DCI JOB NO. 2013-034

TO: Melissa Woods, City of Somerville
Terence Smith, Traffic Engineer

FROM: Jason S. Sobel, P.E., PTOE
Senior Transportation Engineer

SUBJECT: **Parking Assessment**
514C Medford Street
Somerville, MA

DATE: April 30, 2013



This memorandum, prepared at the request of Pennypackers Fine Food, Inc., evaluates the parking needs and on-street parking availability for the property located at 514C Medford Street in Somerville. Pennypackers Fine Food is proposing to open a restaurant at 514C Medford Street, and is seeking zoning relief for three (3) off-street parking spaces.

The purpose of this memo is to evaluate the existing utilization of the the on-street parking and the municipal parking lot parking in the vicinity of the project site. DCI performed a parking survey of available on-street parking on Medford Street and the surrounding streets within approximately 500 feet of the subject property. The study area included the following roadways:

- Medford Street, from Magoun Square to Partridge Avenue
- Lowell Street, from Medford Street to Richardson Street
- Broadway, from Hinckley Street to Strathmore Road
- Cleveland Street, from Harvard Street to Central Street
- Municipal parking lot in Magoun Square (behind CVS)

This study area is shown in Figure 1, below.




Figure 1: Project Study Area

On-street parking on Medford Street and Broadway is generally metered. Parking on Lowell Street is not metered, and is limited to two hours except by residential permit. The following is a list of exceptions:

- On-street parking is prohibited on the west side of Lowell Street.
- On-street parking is prohibited on the south side of Broadway, to the west of Medford Street.

- There is a single handicap only parking space on the south side of Medford Street, near Partridge Avenue.
- There is a single “15 minute only” parking spaces on the south side of Medford Street, just to the east of Lowell Street.
- On the north side of Medford Street to the west of Lowell Street, there is a single loading zone parking space.



On-Street Parking on Medford Street

The loading zone restriction is in place from Monday through Saturday from 9:00am – 5:00pm. This space would be available for passenger vehicle parking after 5:00pm on those days, and throughout the day on Sunday.

- The municipal lot in Magoun Square has several different parking areas. There are 12 metered spaces, 32 numbered spaces that are paid for at a central pay station, two “15 minute only”, three handicap spaces, and two designated Zipcar spaces.

In aggregate, there are approximately 112 existing parking spaces within the study area. This total does *not* include the two Zipcar spaces in the municipal parking lot, the four handicap only spaces (one on-street and three in the municipal parking lot), nor the single loading zone space.

DCI recorded the number of available parking spaces on the study area streets during a typical weekday and during a typical weekend day. The parking data were collected during the following time periods:

Wednesday, April 24, 2013

- 12:00 – 2:00 PM
- 5:00 – 7:00 PM

Saturday April 27, 2013

- 11:00 AM – 2:00 PM

These time periods represent the peak lunch and dinner times when the restaurant is expected to be busiest. The results of the parking surveys are summarized in Table 1. Detailed tables with the complete parking survey data are contained in the attached Appendix.

Table 1 – Summary of Available On-Street and Municipal Parking Spaces

Street		Side	Total Number of Parking Spaces	Average Number of Available Parking Spaces ⁽¹⁾		
				Weekday		Saturday
				Mid-Day	Evening	Mid-Day
Medford Street	North ⁽²⁾	20	10	5	9	
	South ⁽³⁾	19	9	3	7	
Lowell Street	West	<i>no parking</i>				
	East	11	2	1	1	
Broadway	North	10	4	4	3	
	South	6	2	3	2	
Municipal Parking Lot ⁽⁴⁾	Metered	12	7	6	5	
	Numbered	32	23	17	27	
	15-Minute non-metered	2	1	1	1	
Total		112	58	40	55	

Notes:
⁽¹⁾ The average number of available parking spaces is an average of all observations within each observation period
⁽²⁾ Does not include the single loading zone parking space, which is available for use after 5:00pm
⁽³⁾ Does not include the single on-street handicap parking space
⁽⁴⁾ Does not include the two Zipcar spaces, nor the three handicap only parking spaces

As indicated by the parking survey data, an average of 58 parking spaces were available during the weekday mid-day period (12:00 PM to 2:00 PM), and an average of 40 on-street parking spaces were available during the weekday evening period (5:00 PM to 7:00 PM). During the Saturday mid-day observation period (11:00 AM to 2:00 PM), there were an average of 55 available on-street parking spaces. The results of this parking survey indicate that there is a significantly number of unutilized parking spaces on-street



Municipal Parking Lot at Magoun Square

and within the nearby municipal parking lot, more than adequate to accommodate the three parking spaces needed for the 514C Medford Street project. It is also worth noting that there were a minimum of seven (7) available on-street parking spaces on Medford Street in the immediate vicinity of the project site during all observation periods.

In addition to the ample on-street

parking, the Magoun Square area is well served by public transportation. The MBTA Bus Route 80 travels along Broadway and Medford Street, with bus stops less than 400 feet from project site. The Bus Route 80 travels between Arlington Center and Lechmere

Station and provide access to and from the MBTA Green Line. The MBTA Bus Route 89 travels along Broadway between Clarendon Hill or Davis Square and Sullivan Square, and provides connections to the MBTA Red Line and the Orange Line. The bus stops on Broadway are approximately 500 feet from 514C Medford Street. Furthermore, the project site is located approximately 1,300 feet from the future Lowell Street Station, proposed as part of the MBTA Green Line Extension.

Based on the multiple public transportation options that would serve to reduce parking demand in this area, and the significant number of available on-street and municipal parking spaces in the area surrounding the project, it is expected that the existing parking supply will be more than sufficient to support the opening of a restaurant at 514C Medford Street.

Appendix

Parking Survey Data Sheets / Calculations

Design Consultants, Inc.

Parking Survey

Site Location: 514C Medford Street
 City: Somerville, MA
 Date: Wednesday, April 24, 2013
 Weather: cool and cloudy in the AM, warm and sunny in the PM

Proj. No.: 2013-034
 Sheet No.: _____
 Field Tech.: C. Ryan
 Notes: _____

						Weekday - Number of Parked Cars						
						12:00 - 2:00 pm			5:00 - 7:00 pm			
Street	Side	From	To	Notes	Total No. of Spaces	12:30pm to 12:40pm	1:15pm to 1:25pm	1:50pm to 2:00pm	5:20pm to 5:30pm	6:00pm to 6:10pm	6:40pm to 6:50pm	
Medford St	south	Broadway	Lowell St	5 metered 3 unmetered	8	8	4	5	8	8	7	
Lowell St	west	Medford St	Fisk Ave	no parking	0							
Lowell St	west	Fisk Ave	Lowell Terrace	no parking	0							
Lowell St	west	Lowell Terrace	Richardson St	no parking	0							
Lowell St	east	Richardson St	Lowell Terrace	2 hour parking, except by residential permit	3	3	1	2	3	3	3	
Lowell St	east	Lowell Terrace	Medford St	2 hour parking, except by residential permit	8	4	8	7	7	6	8	
Medford St	south	Lowell Street	Trull Street	metered parking	9	2	4	3	6	8	6	
Medford St	south	Trull Street	Partridge Ave	2 regular spaces + 1 HC parking space	2	1	2	2	2	2	2	
Medford St	north	Partridge Ave	Norwood Ave	2 hour parking, except by residential permit	3	3	2	2	3	1	2	
Medford St	north	Norwood Ave	Lowell Street	metered parking	10	6	1	3	8	6	8	
Medford St	north	Lowell Street	Broadway	7 metered spaces +1 "loading zone" space that is available after 5pm	7	5	4	4	5	5	6	
Broadway	south	Magoun Sq	Strathmore Rd	4 metered spaces 2 non-metered 2-hour spaces	6	6	3	3	4	2	2	
Broadway	north	Strathmore Rd	Magoun Sq	5 metered spaces 1 unmetered space	6	3	5	2	1	1	5	
Broadway	north	Magoun Sq	Hinckley St	metered parking	4	4	4	1	3	3	3	
Broadway	south	Hinckley St	Magoun Sq	no parking	0							
Municipal Parking Lot		west row of parking		metered parking	8	4	0	5	2	4	8	
Municipal Parking Lot		west row of parking		numbered parking with central space station	10	1	2	4	1	2	3	
Municipal Parking Lot		south row of parking (including the two spaces that are separated)		15 numbered parking space with central space station + one zip car space	15	4	2	0	3	8	13	
Municipal Parking Lot		north row of parking (including the two parallel spaces next to the building)		7 numbered parking space with central space station + one zip car space	7	4	5	4	5	5	5	
Municipal Parking Lot		east row of parking		metered parking	4	2	1	2	0	1	4	
Municipal Parking Lot		east row of parking		15 min only non-metered spaces	2	2	1	0	1	1	2	
Municipal Parking Lot		east row of parking		HC only, non-metered	3	1	1	0	1	1	1	
Total					112							
Total Number of Cars Parked						62	49	49	62	66	87	
Total Number of Available Spaces						50	63	63	50	46	25	
Average Number of Available Spaces during each period						58.66667			40.33333			

Design Consultants, Inc.

Parking Survey

Site Location: 514C Medford Street
 City: Somerville, MA
 Date: Saturday, April 27, 2013
 Weather: 60 degrees, sunny

Proj. No.: 2013-034
 Sheet No.: _____
 Field Tech.: B. Pyburn
 Notes: _____

						Weekday - Number of Parked Cars					
						11:00 am - 2:00 pm					
Street	Side	From	To	Notes	Total No. of Spaces	11:20am to 11:30am	11:45am to 11:55am	12:15pm to 12:25pm	12:45pm to 12:55pm	1:15pm to 1:25pm	1:45pm to 1:55pm
Medford St	south	Broadway	Lowell St	5 metered 3 unmetered	8	4	4	3	5	5	4
Lowell St	west	Medford St	Fisk Ave	no parking	0						
Lowell St	west	Fisk Ave	Lowell Terrace	no parking	0						
Lowell St	west	Lowell Terrace	Richardson St	no parking	0						
Lowell St	east	Richardson St	Lowell Terrace	2 hour parking, except by residential permit	3	3	3	3	3	3	3
Lowell St	east	Lowell Terrace	Medford St	2 hour parking, except by residential permit	8	8	6	6	6	7	7
Medford St	south	Lowell Street	Trull Street	metered parking	9	6	7	4	6	6	6
Medford St	south	Trull Street	Partridge Ave	2 regular spaces + 1 HC parking space	2	2	2	1	1	2	2
Medford St	north	Partridge Ave	Norwood Ave	2 hour parking, except by residential permit	3	1	1	1	2	0	1
Medford St	north	Norwood Ave	Lowell Street	metered parking	10	4	7	8	7	5	8
Medford St	north	Lowell Street	Broadway	7 metered spaces +1 "loading zone" space that is available after 5pm	7	6	4	2	4	4	4
Broadway	south	Magoun Sq	Strathmore Rd	4 metered spaces 2 non-metered 2-hour spaces	6	4	4	5	5	5	4
Broadway	north	Strathmore Rd	Magoun Sq	5 metered spaces 1 unmetered space	6	4	3	3	3	5	2
Broadway	north	Magoun Sq	Hinckley St	metered parking	4	2	3	3	3	4	4
Broadway	south	Hinckley St	Magoun Sq	no parking	0						
Municipal Parking Lot	west row of parking			metered parking	8	5	4	3	5	4	2
Municipal Parking Lot	west row of parking			numbered parking with central space station	10	1	2	2	2	2	1
Municipal Parking Lot	south row of parking (including the two spaces that are separated)			15 numbered parking space with central space station + one zip car space	15	2	2	1	1	2	1
Municipal Parking Lot	north row of parking (including the two parallel spaces next to the building)			7 numbered parking space with central space station + one zip car space	7	2	2	1	2	1	3
Municipal Parking Lot	east row of parking			metered parking	4	4	4	1	2	2	4
Municipal Parking Lot	east row of parking			15 min only non-metered spaces	2	2	1	0	2	2	2
Municipal Parking Lot	east row of parking			HC only, non-metered	3	2	1	0	0	0	1
Total					112						
Total Number of Cars Parked						60	59	47	59	59	58
Total Number of Available Spaces						52	53	65	53	53	54
Average Number of Available Spaces during each period						55.00000					

**Design Consultants, Inc.
Parking Survey Data Summary**

		Number of Cars Parked													
		Weekday (Wednesday, April 24, 2013)						Saturday, April 27, 2013							
Street	Total Number of Parking Spaces	12:30pm to 12:40pm	1:15pm to 1:25pm	2:00pm to 5:30pm	5:20pm to 6:00pm	6:10pm to 6:50pm	6:40pm to 6:50pm	11:20am to 11:30am	11:30am to 11:45am	11:45am to 12:15pm	12:15pm to 12:25pm	12:25pm to 12:45pm	12:45pm to 1:15pm	1:15pm to 1:25pm	1:25pm to 1:55pm
Medford Street	20	14	7	9	16	12	16	11	12	11	13	9	13	13	
South	19	11	10	10	16	18	15	12	13	8	12	13	12	12	
West	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
East	11	7	9	9	10	9	11	11	9	9	9	9	10	10	
Broadway	10	7	9	3	4	4	8	6	6	6	6	6	9	6	
South	6	6	3	3	4	2	2	4	4	5	5	5	5	4	
Metered	12	6	1	7	2	5	12	9	8	4	7	6	6	6	
Numbered	32	9	9	8	9	15	21	5	6	4	5	5	5	5	
15-Minute non-metered	2	2	1	0	1	1	2	2	1	0	2	2	2	2	
total	112	62	49	49	62	66	87	60	59	47	59	59	59	58	

		Number of Available Spaces													
		Weekday (Wednesday, April 24, 2013)						Saturday, April 27, 2013							
Street	Total Number of Parking Spaces	12:30pm to 12:40pm	1:15pm to 1:25pm	2:00pm to 5:30pm	5:20pm to 6:00pm	6:10pm to 6:50pm	6:40pm to 6:50pm	11:20am to 11:30am	11:30am to 11:45am	11:45am to 12:15pm	12:15pm to 12:25pm	12:25pm to 12:45pm	12:45pm to 1:15pm	1:15pm to 1:25pm	1:25pm to 1:55pm
Medford Street	20	6	13	11	4	8	4	9	8	9	7	11	7	7	
South	19	8	9	9	3	1	4	7	6	11	7	6	6	7	
West	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
East	11	4	2	2	1	2	0	0	2	2	2	2	1	1	
Broadway	10	3	1	7	6	6	2	4	4	4	4	4	1	4	
South	6	0	3	3	2	4	4	2	2	1	1	1	1	2	
Metered	12	6	11	5	10	7	0	3	4	8	5	6	6	6	
Numbered	32	23	23	24	23	17	11	27	26	28	27	27	27	27	
15-Minute non-metered	2	0	1	2	1	1	0	0	1	2	0	0	0	0	
total	112	50	63	63	50	46	25	52	53	65	53	65	53	54	

		Average Number of Available Spaces		
		Weekday		Saturday
Street	Total Number of Parking Spaces	12:00pm to 2:00pm	5:00pm to 7:00pm	11:00am to 2:00pm
Medford Street	20	10.0000	5.3333	8.5000
South	19	8.6667	2.6667	7.3333
West	0	0.0000	0.0000	0.0000
East	11	2.6667	1.0000	1.3333
Broadway	10	3.6667	4.6667	3.5000
South	6	2.0000	3.3333	1.5000
Metered	12	7.3333	5.6667	5.3333
Numbered	32	23.3333	17.0000	27.0000
15-Minute non-metered	2	1.0000	0.6667	0.5000
total	112	58.6667	40.3333	55.0000